DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

United Nations Development Programme

Empowered lives.
Resilient nations.

REQUEST FOR QUOTATION (RFQ)

NAME & ADDRESS OF FIRM:	DATE: 07 June 2019
	REFERENCE: RfQ19/ 01925

Dear Sir / Madam:

We kindly request you to submit your quotation for repair works in the UN House building: 4 bathrooms (1st floor), 2 bathrooms (2nd floor), 1 driver's room, 1 storage room, as detailed in Annex 1 of this RFQ. When preparing your quotation, please be guided by the form attached hereto as Annex 2.

Quotations may be submitted on or before 17 June 2019, **12:30 (Moldova local time)** via e-tendering system to the address below:

https://etendering.partneragencies.org
Username: event.guest
Password: why2change

BU Code: MDA10 and Event 0000003865

Once uploaded, Bidders that have accepted the invitation in the system will be notified via e-mail that changes have occurred. It is responsibility of the Bidder to view the respective changes and clarifications in the system.

Please Consult eTendering Resources for Bidders for additional information on bidding:
http://www.undp.org/content/undp/en/home/operations/procurement/business/procurement-notices/resources/

It shall remain your responsibility to ensure that your quotation will reach the address above on or before the deadline. Quotations that are received by UNDP after the deadline indicated above, for whatever reason, shall not be considered for evaluation.

Please take note of the following requirements and conditions pertaining to the supply of the abovementioned good/s:

Exact Address of Delivery Location (identify all, if multiple)	131, 31 August 1989 Street, MD-2012 Chisinau, Republic of Moldova
Latest Expected Delivery Date and Time *(if delivery time exceeds this, quote may be rejected by UNDP)*	☒ 50 calendar days from the issuance of the Purchase Order (PO)
Delivery Schedule	☒Required

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

Preferred Currency of Quotation	☒Moldovan Lei
Value Added Tax on Price Quotation	☒ Must be inclusive of VAT and other applicable indirect taxes
After-sales services required	☒ Others: Warranty on Works and Materials for a minimum period of 3 (three) years
Deadline for the Submission of Quotation	**17 June 2019, 12:30 (Moldova local time)** IMPORTANT NOTE: the time zone indicated in the Tendering system is New York Time zone. **PLEASE NOTE:** 1. Date and time visible on the main screen of event (on e-tendering portal) will be final and prevail over any other closing time indicated elsewhere, in case they are different. The correct proposal closing time is as indicated in the e-tendering portal and system will not accept any proposal after that time. It is the responsibility of the proposers to make sure proposals are submitted within this deadline. UNDP will not accept any proposal that is not submitted directly in the system. 2. Try to submit your proposal a day prior or well before the closing time. Do not wait until last minute. If you face any issue submitting your proposal at the last minute, UNDP may not be able to assist.
All documentations, including catalogs, instructions and operating manuals, shall be in this language	☒ English ☒ Others: Romanian
Documents to be submitted	☒ Electronic submission of Proposal **https://etendering.partneragencies.org** **Username: event.guest** **Password: why2change** **Please note:** 1. *It is strongly recommended to create your username with two parts, your first name and last name separately by ".", similar to the one shown above.* 2. *You can participate in the proposal event only if you have registered in the system.* ☒ Duly Accomplished Form as provided in Annex 2, and in accordance with the list of requirements in Annex 1; ☒ Company profile (short info up to 1 page); ☒ Copy of Company's Registration Certificate; ☒ Detailed technical description of the offered materials; ☒ Fille-in BOQs (Annex 1), all calculations should be performed using WinSmeta software; ☒ Quality Certificates (ISO, etc.) anr/or other similar certificates, accreditations, awards, citations received by the Bidder, if any; ☒ List of qualified key personnel, together with CVs and professional certificates; ☒List of completed and/or ongoing contracts for similar repair/reconstruction projects for the past 3 (three) years, indicating beneficiary, contract amount, period of execution; ☒Timeframe for execution of works; ☒ Statement of Satisfactory Performance from 2 (two) Clients in the terms of Contract execution (compliance with deadlines, quality of the works, reasonableness of the value of the contract);

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

	☒ Written Self-Declaration of not being included in the UN Security Council 1267/1989 list, UN Procurement Division List or other UN Ineligibility List.
Period of Validity of Quotes starting the Submission Deadline Date	☒ 90 days In exceptional circumstances, UNDP may request the Vendor to extend the validity of the Quotation beyond what has been initially indicated in this RFQ. The Proposal shall then confirm the extension in writing, without any modification whatsoever on the Quotation.
Partial Quotes	☒ Not permitted
Payment Terms[1]	☒ 100% upon complete delivery of goods
Liquidated Damages	0.25% of contract for every day of delay, up to a maximum duration of 1 calendar month. Thereafter, the contract may be terminated.
Evaluation Criteria	☒ Technical responsiveness/Full compliance to requirements and lowest price[2]; ☒ Minimum 3 (three) years experience in the construction field; ☒ Availability of certificates of quality and origin for the offered materials; ☒Warranty on Works and Materials for a minimum period of 3 (three) years ; ☒ Full acceptance of the PO/Contract General Terms and Conditions
UNDP will award to:	☒ One and only one supplier
Type of Contract to be Signed	☒ Purchase Order
Special conditions of Contract	☒ Cancellation of PO/Contract if the delivery/completion is delayed by 30 days
Conditions for Release of Payment	☒ Passing inspection; ☒ Completion of works; ☒ Written Acceptance of Works based on full compliance with RFQ requirements.
Annexes to this RFQ	☒ Specifications of the Works Required (Annex 1) ☒ Form for Submission of Quotation (Annex 2) ☒ General Terms and Conditions / Special Conditions (Annex 3). Non-acceptance of the terms of the General Terms and Conditions (GTC) shall be grounds for disqualification from this procurement process.
Contact Person for Inquiries (Written inquiries only)[3]	Alisa Zaiteva, UN House Admin&Finance Assistant alisa.zaiteva@one.un.org Any delay in UNDP's response shall be not used as a reason for extending the deadline for submission, unless UNDP determines that such an extension is necessary and communicates a new deadline to the Proposers.

[1] *UNDP preference is not to pay advanced amount upon signing of contract. If vendor strictly requires advanced payment, it will be limited only up to 20% of the total price quoted. For any higher percentage, or advanced payment of $30,000 or higher, UNDP shall require the vendor to submit a bank guarantee or bank checque payable to UNDP, in the same amount as the advanced payment made by UNDP to the vendor.*

[2] *UNDP reserves the right not to award the contract to the lowest priced offer, if the second lowest price among the responsive offer is found to be significantly more superior, and the price is higher than the lowest priced compliant offer by not more than 10%, and the budget can sufficiently cover the price difference. The term "more superior" as used in this provision shall refer to offers that have exceeded the pre-determined requirements established in the specifications.*

[3] *This contact person and address is officially designated by UNDP. If inquiries are sent to other person/s or address/es, even if they are UNDP staff, UNDP shall have no obligation to respond nor can UNDP confirm that the query was received.*

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

Goods offered shall be reviewed based on completeness and compliance of the quotation with the minimum specifications described above and any other annexes providing details of UNDP requirements.

The quotation that complies with all of the specifications, requirements and offers the lowest price, as well as all other evaluation criteria indicated, shall be selected. Any offer that does not meet the requirements shall be rejected.

Any discrepancy between the unit price and the total price (obtained by multiplying the unit price and quantity) shall be re-computed by UNDP. The unit price shall prevail and the total price shall be corrected. If the supplier does not accept the final price based on UNDP's re-computation and correction of errors, its quotation will be rejected.

After UNDP has identified the lowest price offer, UNDP reserves the right to award the contract based only on the prices of the goods in the event that the transportation cost (freight and insurance) is found to be higher than UNDP's own estimated cost if sourced from its own freight forwarder and insurance provider.

At any time during the validity of the quotation, no price variation due to escalation, inflation, fluctuation in exchange rates, or any other market factors shall be accepted by UNDP after it has received the quotation. At the time of award of Contract or Purchase Order, UNDP reserves the right to vary (increase or decrease) the quantity of services and/or goods, by up to a maximum twenty five per cent (25%) of the total offer, without any change in the unit price or other terms and conditions.

Any Purchase Order that will be issued as a result of this RFQ shall be subject to the General Terms and Conditions attached hereto. The mere act of submission of a quotation implies that the vendor accepts without question the General Terms and Conditions of UNDP herein attached as Annex 3.

UNDP is not bound to accept any quotation, nor award a contract/Purchase Order, nor be responsible for any costs associated with a Supplier's preparation and submission of a quotation, regardless of the outcome or the manner of conducting the selection process.

Please be advised that UNDP's vendor protest procedure is intended to afford an opportunity to appeal for persons or firms not awarded a purchase order or contract in a competitive procurement process. In the event that you believe you have not been fairly treated, you can find detailed information about vendor protest procedures in the following link: http://www.undp.org/procurement/protest.shtml.

UNDP encourages every prospective Vendor to avoid and prevent conflicts of interest, by disclosing to UNDP if you, or any of your affiliates or personnel, were involved in the preparation of the requirements, design, specifications, cost estimates, and other information used in this RFQ.

UNDP implements a zero tolerance on fraud and other proscribed practices, and is committed to identifying and addressing all such acts and practices against UNDP, as well as third parties involved in UNDP activities. UNDP expects its suppliers to adhere to the UN Supplier Code of Conduct found in this link : http://www.un.org/depts/ptd/pdf/conduct_english.pdf.

Thank you and we look forward to receiving your quotation.

Sincerely yours,

Denis Suschevici

Denis Suschevici
ARR Operations a.i.

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

Annex 1

Specifications of works required (Caiet de sarcini)

Lucrari de reparatie in incinta Cladirii ONU, mun. Chisinau, str. 31 August 1989, nr. 131

№ crt.	Simbol norme şi Cod resurse	Lucrări şi cheltuieli	U.M.	Cantitate conform datelor din proiect	Valoare de deviz, lei	
					Pe unitate de măsură incl. salariu	Total incl. salariu
1	2	3	4	5	6	7
1. Subsol - Oficiu soferi						
		1. Finisare pereti				
1	RpCJ35A	Desfaceri de tencuieli interioare sau exterioare driscuite la pereti sau tavane	m2	21,70		
2	IzF31B	Hidroizolarea suprafetelor din beton (verticale, orizontale,inclusiv tavane) cu amestec "Penetron" - 2 straturi: suprafata rugoasa	m2	19,10		
3	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	2,60		
4	CF15A	Tencuieli interioare si exterioare sclivisite, executate manual, cu mortar de ciment M 100-T de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	21,70		
5	CF17B k=3	Diverse lucrari - diferenta de grosime, +- 5 mm la stratul de grund aplicat la pereti, executat cu mortar ciment M100 Коэффициент к трудозатратам=3,0000 Коэффициент к материалам=3,0000 Коэффициент к машинам=3,0000	m2	21,70		
6	CF17C	Strat de impaslitura din fibra de sticla greutate 80 kg/m2, aplicat in componenta tencuelii cu amestec uscat	m2	21,70		
7	CF50B	Tencuieli interioare de 5 mm grosime, executate manual, cu amestec uscat pe baza de ipsos, la pereti si pereti despartitori, preparare manuala a mortarului.	m2	21,70		
8	CK18C	Montarea cornierilor perforate din aluminiu la colturi glafuri	m	7,95		
9	CF57A	Aplicarea manuala a chitului pe baza de ipsos grosime 1,0 mm pe suprafetele peretilor, coloanelor si a tavanelor	m2	21,70		
10	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	55,00		
11	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie	m2	55,00		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

1	2	3	4	5	6	7
		apoasa, aplicate in 2 straturi pe glet existent, executate manual				
12	CF17D	Diverse lucrari - adaos de colorant	kg	0,55		
13	RpIB11D	Demontarea radiatoarelor de incalzire	buc	3,00		
14	IB06A	Radiatoare din otel, monobloc avind lungimea de pina la 1000 mm, inclusiv (existente)	buc	3,00		
		Total	lei			
		Total Finisare pereti Inclusiv salariu				
		2. Finisare tavan				
15	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	36,00		
16	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual	m2	36,00		
		Total	lei			
		Total Finisare tavan Inclusiv salariu				
		3. Finisare pardosele				
17	RpCK41A	Desfacerea pardoselilor din dusumele din scindura, dulapi, etc	m2	31,10		
18	CA02C	Cimentoplast cu densitatea D=400 kg/m3, turnat la pardosele Material marunt (dulapi de rasinoase)=1,0100	m3	3,11		
19	CG01A	Strat suport pentru pardoseli executat din mortar din ciment M 100-T de 3 cm grosime cu fata driscuita fin	m2	31,10		
20	CC03C	Montare plase sudate d=3.0 mm, ochi 100x100 mm, la inaltimi mai mici sau egale cu 35 m, la placi (1.0 kg/m2)	kg	31,10		
21	CG01A1 k=2	Diferenta in plus sau in minus pentru fiecare 0,5 cm de strat suport din mortar M 100-T, se adauga sau se scade Coeficient la manoperei=2,0000 Coeficient la utilajului=2,0000 Coeficient la pentru materiale=2,0000	m2	31,10		
22	CG56A	Sapa din amestec de autonivelare "Nivelir": grosime 10mm Material marunt (polistiren expandat pentru rosturi de deformatie, cirpe, martori)=1,0050	m2	31,10		
23	CG56A1	Corectia la norma CG56A: se scade la 1mm grosime: k=5 Coeficient la manoperei=5,0000 Coeficient la pentru materiale=5,0000 Coeficient la utilajului=5,0000	m2	-31,10		
24	CG36A	Pardoseli din placi laminat trafic comercial intens, grosime 10 mm, montale pe uscat cu pozarea stratului sintetic pe suport existent, inclusiv plintele de lemn si curatarea, in incaperii mai mare de 16 mp Materiale marunte (cuie)=1,0100	m2	31,10		
		Total	lei			

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

1	2	3	4	5	6	7
		Total Finisare pardosele Inclusiv salariu				
		4. Timplarie				
25	RpCO56A	Demontari: timplarie din lemn (usi, ferestre, obloane, cutii, rulou, masti, etc.)	m2	1,75		
26	CK03A	Usi din lemn interioare intr-un canat, din MDF, inclusiv pervazurile, montate pe ghermele existente	m2	1,75		
27	CK33C	Broasca aplicata sistem Yalle	buc	1,00		
		Total	lei			
		Total Timplarie Inclusiv salariu				
		5. Instalatii electrice				
28	08-02-409-1	Teava din vinilplast pe contructii instalate, fixare cu scoabe, diametru pina la 25 mm	100 m	0,25		
29	pret furnizor	Teava PE p/u electromontaj d=20 mm	m.l.	25,00		
30	08-02-412-10	Introducerea conductorilor in tevi si furtunuri metalice pozate: fiecare conductor urmator monofir sectiune sumara pina la 35 mm2	100 m	0,30		
31	pret furnizor	Cablu ВВГнг-LSL Tx-0.66 3x2.5 mm2	m.l.	6,00		
32	pret furnizor	Cablu ВВГнг-LSL Tx-0.66 5x4 mm2	m.l.	24,00		
33	pret furnizor	Cutie de distributie, IP31, 130x130x80 mm	buc	5,00		
34	08-03-591-9	Priza de fisa tip neingropat, la instalatie inchisa	100 buc	0,18		
35	pret furnizor	Priza instalatie inchisa cu legare la pamint, IP20, 16A, 220V	buc	18,00		
36	08-03-591-5	Intreruptor cu doua clape, tip neingropat, la instalatie inchisa	100 buc	0,01		
37	pret furnizor	Intrerupator instalatie inchisa cu legare la pamint, cu 2 clape, IP20, 10A, 220V	buc	1,00		
38	pret furnizor	Doze pentru aparate	buc	18,00		
39	08-03-594-1	Corp de iluminat cu lampi led, cantitate lampi, in corp de iluminat, 1	100 buc	0,06		
40	pret furnizor	Corp de iluminat montat in tavan, cu sursa de iluminat LED, 40W, IP20, 4000K, 3200 Lm	buc	6,00		
		Total	lei			
		Total Instalatii electrice Inclusiv salariu				

2. Subsol – Incaperea pentru serviciul gospodarie						
		1. Finisare pereti				
1	RpCJ35A	Desfaceri de tencuieli interioare sau exterioare driscuite la pereti sau tavane	m2	34,50		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

2	IzF31B	Hidroizolarea suprafetelor din beton (verticale, orizontale,inclusiv tavane) cu amestec "Penetron" - 2 straturi: suprafata rugoasa	m2	7,30		
3	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	27,20		
4	CF15A	Tencuieli interioare si exterioare sclivisite, executate manual, cu mortar de ciment M 100-T de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	34,50		
5	CF17B k=3	Diverse lucrari - diferenta de grosime, +- 5 mm la stratul de grund aplicat la pereti, executat cu mortar ciment M100 Коэффициент к трудозатратам=3,0000 Коэффициент к материалам=3,0000 Коэффициент к машинам=3,0000	m2	34,50		
6	CF17C	Strat de impaslitura din fibra de sticla greutate 80 kg/m2, aplicat in componenta tencuelii cu amestec uscat	m2	34,50		
7	CF50B	Tencuieli interioare de 5 mm grosime, executate manual, cu amestec uscat pe baza de ipsos, la pereti si pereti despartitori, preparare manuala a mortarului.	m2	34,50		
8	CK18C	Montarea cornierilor perforate din aluminiu la colturi glafuri	m	5,10		
9	CF57A	Aplicarea manuala a chitului pe baza de ipsos grosime 1,0 mm pe suprafetele peretilor, coloanelor si a tavanelor	m2	34,10		
10	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	34,10		
11	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual	m2	34,10		
12	CF17D	Diverse lucrari - adaos de colorant	kg	0,35		
13	08-02-390-3	Canale din masa plastica cu sectiunea 100x60 mm, inclusiv montarea accesoriilor (coturi, teuri, cruci)	100 m	0,08		
		Total	lei			
		Total Finisare pereti Inclusiv salariu				
		2. Finisare tavane				
14	RpCJ35A	Desfaceri de tencuieli interioare sau exterioare driscuite la pereti sau tavane	m2	16,60		
15	CN53A	Grunduirea suprafetelor interioare cu grund tip "Betonokontakt"	m2	16,60		
16	CF52B	Tencuieli interioare de 5 mm grosime, executate manual, cu amestec uscat pe baza de ipsos, la	m2	16,60		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		tavan, preparare manuala a mortarului				
17	CF17C	Strat de impaslitura din fibra de sticla greutate 80 kg/m2, aplicat in componenta tencuelii cu amestec uscat	m2	16,60		
18	CK18C	Montarea cornierilor perforate din aluminiu la colturi glafuri	m	8,20		
19	CF57A	Aplicarea manuala a chitului pe baza de ipsos grosime 1,0 mm pe suprafetele peretilor, coloanelor si a tavanelor	m2	16,60		
20	CN53A	Grunduirea suprafetelor interioare sau exterioare cu grund cu patrundere adinca de tip "Tuffuhgpuht"	m2	16,60		
21	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual	m2	16,60		
		Total	lei			
		Total Finisare tavane Inclusiv salariu				
		3. Finisare pardosele				
22	RpCK42C	Desfacerea pardoselilor reci din placi de beton, marmura, piatra, gresie, placi ceramice, etc	m2	14,05		
23	CG56A	Sapa din amestec de autonivelare "Nivelir": grosime 10mm Material marunt (polistiren expandat pentru rosturi de deformatie, cirpe, martori)=1,0050	m2	14,05		
24	CN53A	Grunduirea suprafetelor interioare cu grund tip "Betonokontakt"	m2	14,05		
25	CG17D1	Pardoseli din placi de gresie, 300x300x8 mm, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	14,05		
26	CI14A	Elemente liniare din placi din gresie ceramica h=10 cm aplicate cu adeziv Material marunt (cirpe, apa etc)=1,0500	m	15,30		
		Total	lei			
		Total Finisare pardosele Inclusiv salariu				
		4. Timplarie				
27	RpCO56A	Demontari: timplarie din lemn (usi, ferestre, obloane, cutii, rulou, masti, etc.)	m2	1,89		
28	CK03A	Usi din lemn interioare intr-un canat, din MDF, inclusiv pervazurile, montate pe ghermele existente	m2	1,89		
29	CK33C	Broasca aplicata sistem Yalle	buc	1,00		
		Total	lei			
		Total Timplarie Inclusiv salariu				
		5. Instalatii electrice				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

30	08-02-409-1	Teava din vinilplast pe contructii instalate, fixare cu scoabe, diametru pina la 25 mm	100 m	0,02		
31	pret furnizor	Teava PE p/u electromontaj d=20 mm	m.l.	2,00		
32	08-02-412-10	Introducerea conductorilor in tevi si furtunuri metalice pozate: fiecare conductor urmator monofir sectiune sumara pina la 35 mm2	100 m	0,02		
33	pret furnizor	Cablu ВВГнг-LSL Tx-0.66 3x2.5 mm2	m.l.	2,00		
34	08-03-591-9	Priza de fisa tip neingropat, la instalatie inchisa	100 buc	0,03		
35	pret furnizor	Priza instalatie inchisa cu legare la pamint, IP20, 16A, 220V	buc	3,00		
36	08-03-591-5	Intreruptor cu doua clape, tip neingropat, la instalatie inchisa	100 buc	0,01		
37	pret furnizor	Intrerupator instalatie inchisa cu legare la pamint, cu 2 clape, IP20, 10A, 220V	buc	1,00		
38	pret furnizor	Doze pentru aparate	buc	4,00		
39	08-03-594-1	Corp de iluminat cu lampi led, cantitate lampi, in corp de iluminat, 1	100 buc	0,02		
40	pret furnizor	Corp de iluminat montat in tavan, cu sursa de iluminat LED, 40W, IP20, 4000K, 3200 Lm	buc	2,00		
		Total	lei			
		Total Instalatii electrice Inclusiv salariu				

3. Etajul 1 – Bloc sanitar (incaperea nr.14)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	1,6000		
2	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	16,0000		
3	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	16,0000		
4	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	1,6000		
5	RpCO56C	Demontari: tavane suspendate	m2	1,6000		
6	RpCO56A	Demontari: timplarie din lemn (usi)	m2	1,4700		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

7	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	1,0000		
8	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
9	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
10	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
11	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
12	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
13	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	1,0400		
14	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	1,0400		
15	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	1,0400		
16	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	1,0400		
		Total	lei			
		Total Lucrari de demolare Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **1.2.1. Pereti**				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

17	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	16,0000		
18	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	16,0000		
19	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	16,0000		
		Total	lei			
		Total Pereti Inclusiv salariu				
		1.2.2. Tavane				
20	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	2,6500		
21	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	2,6500		
22	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	2,6500		
23	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)	m2	2,6500		
		Total	lei			
		Total Tavane Inclusiv salariu				
		1.2.3. Pardoseli				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

24	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	1,6000		
25	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	1,6000		
26	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	1,6000		
		Total	lei			
		Total Pardoseli Inclusiv salariu				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) Inclusiv salariu				
		1.3. Timplarii				
27	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 700x2100(h) - 1buc	m2	1,4700		
		Total	lei			
		Total Timplarii Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		2.1. Retele tehnico-sanitare				
28	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
29		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
30	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
31	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
32	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic, montat pe console fixate pe pereti din zidarie de caramida sau b.c.a. cu mobilier	buc	1,0000		
33	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		
34	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		
35	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
36	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
37	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
38	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		

4. Etajul 1 – Bloc sanitar (incaperea nr.16)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	2,0600		
2	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	17,0000		
3	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	17,0000		
4	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	2,0600		
5	RpCO56C	Demontari: tavane suspendate	m2	2,0600		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

6	RpCO56A	Demontari: timplarie din lemn (usi)	m2	1,8900		
7	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	1,0000		
8	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
9	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
10	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
11	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
12	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
13	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	1,7400		
14	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	1,7400		
15	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	1,7400		
16	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	1,7400		
		Total	lei			
		Total Lucrari de demolare Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare)				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		1.2.1. Pereti				
17	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	15,0000		
18	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	15,0000		
19	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	15,0000		
		Total	lei			
		Total Pereti **Inclusiv salariu**				
		1.2.2. Tavane				
20	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	2,0600		
21	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	2,0600		
22	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	2,0600		
23	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)	m2	2,0600		
		Total	lei			
		Total Tavane **Inclusiv salariu**				
		1.2.3. Pardoseli				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

24	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	2,0600		
25	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	2,0600		
26	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	2,0600		
		Total	lei			
		Total Pardoseli Inclusiv salariu				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) Inclusiv salariu				
		1.3. Timplarii				
27	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 9000x2100(h) - 1buc	m2	1,8900		
28	CL21A	Elemente de suport pentru persoane cu dezabilitati din teava de inox diam.30mm, inclusiv elementele de fixare (3 seturi)	m	2,4000		
		Total	lei			
		Total Timplarii Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare **2.1. Retele tehnico-sanitare**				
29	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
30		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
31	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
32	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
33	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic, montat pe console fixate pe pereti din zidarie de caramida sau b.c.a.	buc	1,0000		
34	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		
35	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

36	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		
		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
37	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
38	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
39	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		

5. Etajul 1 – Bloc sanitar (incaperea nr.25)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	2,6500		
2	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	18,0000		
3	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	18,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

4	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	2,6500		
5	RpCO56C	Demontari: tavane suspendate	m2	2,6500		
6	RpCO56A	Demontari: timplarie din lemn (usi)	m2	1,4700		
7	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	1,0000		
8	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
9	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
10	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
11	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
12	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
13	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	1,8900		
14	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	1,8900		
15	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	1,8900		
16	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	1,8900		
		Total	lei			
		Total Lucrari de demolare				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **1.2.1. Pereti**				
17	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	18,0000		
18	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	18,0000		
19	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	18,0000		
		Total	lei			
		Total Pereti **Inclusiv salariu**				
		1.2.2. Tavane				
20	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	2,6500		
21	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	2,6500		
22	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	2,6500		
23	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)	m2	2,6500		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total	lei			
		Total Tavane **Inclusiv salariu**				
		1.2.3. Pardoseli				
24	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	2,6500		
25	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	2,6500		
26	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	2,6500		
		Total	lei			
		Total Pardoseli **Inclusiv salariu**				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **Inclusiv salariu**				
		1.3. Timplarii				
27	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 700x2100(h) - 1buc	m2	1,4700		
		Total	lei			
		Total Timplarii **Inclusiv salariu**				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare **2.1. Retele tehnico-sanitare**				
28	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
29		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
30	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
31	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
32	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic, montat pe console fixate pe pereti din zidarie de caramida sau b.c.a. cu mobilier	buc	1,0000		
33	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		
34	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

35	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		
		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
36	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
37	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
38	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		

6. Etajul 1 – Bloc sanitar (incaperea nr.26)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	2,6500		
2	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	18,0000		
3	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	18,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

4	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	2,6500		
5	RpCO56C	Demontari: tavane suspendate	m2	2,6500		
6	RpCO56A	Demontari: timplarie din lemn (usi)	m2	1,4700		
7	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	1,0000		
8	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
9	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
10	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
11	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
12	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
13	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	1,8900		
14	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	1,8900		
15	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	1,8900		
16	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	1,8900		
		Total	lei			
		Total Lucrari de demolare				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **1.2.1. Pereti**				
17	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	18,0000		
18	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	18,0000		
19	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	18,0000		
		Total	lei			
		Total Pereti **Inclusiv salariu**				
		1.2.2. Tavane				
20	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	2,6500		
21	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	2,6500		
22	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	2,6500		
23	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)	m2	2,6500		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total	lei			
		Total Tavane **Inclusiv salariu**				
		1.2.3. Pardoseli				
24	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	2,6500		
25	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	2,6500		
26	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	2,6500		
		Total	lei			
		Total Pardoseli **Inclusiv salariu**				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **Inclusiv salariu**				
		1.3. Timplarii				
27	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 700x2100(h) - 1buc	m2	1,4700		
		Total	lei			
		Total Timplarii **Inclusiv salariu**				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare **2.1. Retele tehnico-sanitare**				
28	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
29		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
30	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
31	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
32	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic, montat pe console fixate pe pereti din zidarie de caramida sau b.c.a. cu mobilier	buc	1,0000		
33	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		
34	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

35	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		
		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
36	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
37	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
38	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		

7. Etajul 2 – Blocul sanitar (incaperea nr.19)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCG29A	Demolarea peretilor de zidarie din caramida	m2	4,0800		
2	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	3,6500		
3	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	22,7000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

4	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	22,7000		
5	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	3,6500		
6	RpCO56C	Demontari: tavane suspendate	m2	3,6500		
7	RpCO56A	Demontari: timplarie din lemn (usi)	m2	2,9400		
8	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	2,0000		
9	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
10	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
11	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
12	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
13	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
14	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	3,4700		
15	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	3,4700		
16	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	3,4700		
17	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	3,4700		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total	lei			
		Total Lucrari de demolare Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **1.2.1. Pereti**				
18	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	22,7000		
19	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	22,7000		
20	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	22,7000		
		Total	lei			
		Total Pereti Inclusiv salariu				
		1.2.2. Tavane				
21	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	3,6500		
22	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	3,6500		
23	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	3,6500		
24	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol	m2	3,6500		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)				
		Total	lei			
		Total Tavane **Inclusiv salariu**				
		1.2.3. Pardoseli				
25	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	3,6500		
26	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	3,6500		
27	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	3,6500		
		Total	lei			
		Total Pardoseli **Inclusiv salariu**				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **Inclusiv salariu**				
		1.3. Timplarii				
28	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 700x2100(h) - 1buc	m2	1,4700		
		Total	lei			
		Total Timplarii **Inclusiv salariu**				
		Total	lei			
		Asigurarea sociala si medicala				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare **2.1. Retele tehnico-sanitare**				
29	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
30		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
31	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
32	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
33	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic, montat pe console fixate pe pereti din zidarie de caramida sau b.c.a. cu mobilier	buc	1,0000		
34	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

35	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		
36	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		
		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
37	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
38	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
39	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		

8. Etajul 2 – Blocul sanitar (incaperea nr.22)						
		1. Lucrari de constructie **1.1. Lucrari de demolare**				
1	RpCG29A	Demolarea peretilor de zidarie din caramida	m2	5,6400		
2	RpCK42C	Desfacerea pardoselilor reci din placi de gresie, placi ceramice, etc	m2	4,4000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

3	RpCM33A	Demontarea placajelor din faianta, gresie, ceramica	m2	23,0000		
4	RpCJ35A	Desfaceri de tencuieli interioare driscuite la pereti, inclusiv teracota	m2	23,0000		
5	RpCK42A	Desfacerea pardoselilor reci din mortar de ciment	m2	4,4000		
6	RpCO56C	Demontari: tavane suspendate	m2	4,4000		
7	RpCO56A	Demontari: timplarie din lemn (usi)	m2	3,3600		
8	RpEF23A	Demontari de corpuri de iluminat orice tip	buc	2,0000		
9	RpSC06A	Demontarea unui vas de closet din faianta, complet echipat	buc	1,0000		
10	RpSC05A	Demontarea unui lavoar de faianta, inclusiv accesoriile	buc	1,0000		
11	RpSD01A	Demontarea unui robinet simplu serviciu sau cu racord, avind diametru de 3/8"-1/2"	buc	3,0000		
12	RpSD03A	Demontarea unei baterii stative, avind diametru de 1/2"	buc	1,0000		
13	RpSA04A	Demontarea tevii din policrorura de vinil neplastifiat tip greu existenta in interiorul cladirii, la legaturi, coloane, sau conducte de distributie, avind diametru de 12 mm - 50 mm	m	2,0000		
14	TrB01A2-1	Transportul materialelor din grupa 4 (mortar, beton), cu roabe pe pneuri, pe distanta de 10 m	t	4,0100		
15	TrI1AA02 B3	Incarcarea materialelor din grupa A - grele, in bulgari prin aruncare - de pe teren, in containere, categoria 3	t	4,0100		
16	TrB22D1C 1	Incarcarea materialelor cu macaraua pe pneuri, de 10 tf, amplasata in pozitie fixa, greutatea materialelor 1-1,5 t si inaltimea de ridicare fiind de 0-6 m	t	4,0100		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

17	TsI51A10	Transportarea deseuri cu autobasculanta de 10 t la distanta de 10 km	t	4,0100		
		Total	lei			
		Total Lucrari de demolare Inclusiv salariu				
		1.2. Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **1.2.1. Pereti**				
18	RpCJ12A	Tencuieli interioare sclivisite, executate cu mortar de ciment-nisip M 50 de 2 cm grosime medie, la pereti din beton sau caramida, cu suprafete plane	m2	23,0000		
19	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	23,0000		
20	CI22B	Placaj din placute de ceramica calit 1, (la pereti, stilpi, pilastri si glafuri) fixate de adeziv (amestec uscat)	m2	23,0000		
		Total	lei			
		Total Pereti Inclusiv salariu				
		1.2.2. Tavane				
21	CF59D	Placarea suprafetelor cu un strat de PGC 12,5mm hidrofug, cu grunduirea si chituirea suprafetei rosturilor, cu executarea carcasei metalice simple plane, cu inaltimea pina la 4 m: tavane fara izolatie	m2	4,4000		
22	CF57A	Aplicarea manuala a chitului pe baza de ipsos "Eurofin" grosime 1,0 mm pe suprafetele peretilor, coloanelor si tavanelor	m2	4,4000		
23	CN53A	Grunduirea suprafetelor interioare a tavanelor cu grund "CapaSol" sau analog ca nivel de calitate	m2	4,4000		
24	CN06A	Vopsitorii interioare cu vopsea pe baza de copolimeri vinilici in	m2	4,4000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		emulsie apoasa, aplicate in 2 straturi pe glet existent, executate manual, cu vopsea "Caparol Sensitiv" sau analog ca nivel de calitate, (aplicativ, consum vopsea 0,28 kg/m2)				
		Total	lei			
		Total Tavane **Inclusiv salariu**				
		1.2.3. Pardoseli				
25	CG01A	Strat suport pentru pardoseli executat din mortar din ciment-nisip semiuscat M 100-T de 3 cm grosime cu fata driscuita fin	m2	4,4000		
26	CN54A	Aplicarea manuala a grundului cu cuart "Betonocontact" sau analog intr-un strat	m2	4,4000		
27	CG17D1	Pardoseli din placi de gresie ceramica antiderapanta gr. min. 8mm, calit. 1, rezist. abraziune cl. PEI 3 EN ISO 10 545, inclusiv stratul suport din mortar adeziv, executate pe suprafete: egale sau mai mici de 16 m2	m2	4,4000		
		Total	lei			
		Total Pardoseli **Inclusiv salariu**				
		Total	lei			
		Total Lucrari de reparatie (ofertantul indica in devizul oferta materialele propuse pentru aplicare) **Inclusiv salariu**				
		1.3. Timplarii				
28	CK03A	Usi din MDF interioare intr-un canat, pe captuseli si usi pentru balcon, inclusiv izolatia hidrofuga si termica a tocului, montate pe ghermele existente la constructii cu inaltimi pina la 35 m 9000x2100(h) - 1buc	m2	1,8900		
29	CL21A	Elemente de suport pentru persoane cu dezabilitati din teava de inox diam.30mm, inclusiv elementele de fixare (3 seturi)	m	2,4000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Total	lei			
		Total Timplarii Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari de constructie Inclusiv salariu				
		2. Lucrari tehnico-sanitare **2.1. Retele tehnico-sanitare**				
30	SA20A	Teava din material plastic imbinata prin sudura prin electrofuziune, in conducte de legatura la obiecte sanitare la cladiri de locuit si social culturale, avind diametrul de 20 mm / Teava de polipropilena PN10 ϕ20x2,8	m	2,0000		
31		Racord FE PP ϕ1/2"x1/2"	buc	3,0000		
32	SD05A	Robinet de reglaj, drept sau coltar, montat inaintea armaturii de la obiectele sanitare, avind diametrul de 1/2"	buc	3,0000		
		Total	lei			
		Total Retele tehnico-sanitare Inclusiv salariu				
		2.2. Obiecte sanitare				
33	SC07A1	Vas pentru closet, complet echipat, din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, asezat pe pardoseala, cu rezervorul de apa montat pe vas, la inaltime sau semiinaltime, avind sifonul interior tip S	buc	1,0000		
34	SC04A	Lavoar din semiportelan, portelan sanitar etc. inclusiv pentru handicapati, avind teava de scurgere din material plastic,	buc	1,0000		

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		montat pe console fixate pe pereti din zidarie de caramida sau b.c.a.				
35	SD03A	Robinet pentru lavoar, indiferent de modul de inchidere, inclusiv pentru handicapati, avind diametrul de 1/2"	buc	1,0000		
36	SE59A	Uscator de mini sau distribuitor automat de sapun lichid, montat pe perete din caramida sau b.c.a.	buc	1,0000		
37	SC13A	Oglinda sanitara din semicristal cu marginile slefuite, montata pe perete din zidarie de caramida sau b.c.a.	buc	1,0000		
		Total	lei			
		Total Obiecte sanitare Inclusiv salariu				
		Total	lei			
		Asigurarea sociala si medicala				
		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total Lucrari tehnico-sanitare Inclusiv salariu				
		3. Lucrari de electromontare				
38	RpEA05A	Montarea tubului flexibil izolant, usor, cu invelis flexibil din material plactic (IPFY), avind diametrul pina la 15 mm	m	2,0000		
39	RpED09A	Montarea cablurilor electrice din cupru, cu izolatie din PVC, cu rezistenta marita la propagarea flacarilor, pentru tensiuni de 0,6/1 kV, simbol CYYF, montate aparent, avind sectiunea de 3x1,5 mmp	m	2,0000		
40	RpEF13A	Montarea corpurilor de iluminat de 60 W	buc	1,0000		
		TOTAL:				
		Asigurarea sociala si medicala				

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

		Transportul materialelor				
		Cheltuieli de achizitionare-depozitare				
		Total				
		Cheltuieli de regie				
		Total				
		Beneficiu de deviz				
		Total				
		TVA				
		Total deviz: Inclusiv salariu				

Annex 2

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

FORM FOR SUBMITTING SUPPLIER'S QUOTATION[4]

(This Form must be submitted only using the Supplier's Official Letterhead/Stationery[5])

We, the undersigned, hereby accept in full the UNDP General Terms and Conditions, and hereby offer to supply the items listed below in conformity with the specification and requirements of UNDP as per RFQ Reference No. RfQ19/01925:

TABLE 1: Offer to Supply Goods Compliant with Technical Specifications and Requirements

Description of Activity/Item		Total estimated amount in MDL, VAT included
1	**Repair works in the UN House building: 4 bathrooms (1st floor), 2 bathrooms (2nd floor), 1 driver's room, 1 storage room**	

TABLE 2: List of qualified key personnel

#	Name	Education	Work Experience	Role in contract implementation
1				
2				
3				
.				
10				

TABLE 3 : Offer to Comply with Other Conditions and Related Requirements

Other Information pertaining to our Quotation are as follows:	Your Responses		
	Yes, we will comply	***No, we cannot comply***	***If you cannot comply, pls. indicate counter proposal***
Delivery Lead Time (50 calendar days)			
Warranty and After-Sales Requirements:			
a) Minimum 3 (three) years warranty on works			
b) Minimum 3 (three) years warranty on materials			
Validity of Quotation (90 days)			
All Provisions of the UNDP General Terms and Conditions			

All other information that we have not provided automatically implies our full compliance with the requirements, terms and conditions of the RFQ.

[Name and Signature of the Supplier's Authorized Person]
[Designation]
[Date]

[4] *This serves as a guide to the Supplier in preparing the quotation and price schedule.*
[5] *Official Letterhead/Stationery must indicate contact details – addresses, email, phone and fax numbers – for verification purposes*

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

Annex 3

General Terms and Conditions

1. ACCEPTANCE OF THE PURCHASE ORDER

This Purchase Order may only be accepted by the Supplier's signing and returning an acknowledgement copy of it or by timely delivery of the goods in accordance with the terms of this Purchase Order, as herein specified. Acceptance of this Purchase Order shall effect a contract between the Parties under which the rights and obligations of the Parties shall be governed solely by the terms and conditions of this Purchase Order, including these General Conditions. No additional or inconsistent provisions proposed by the Supplier shall bind UNDP unless agreed to in writing by a duly authorized official of UNDP.

2. PAYMENT

2.1 UNDP shall, on fulfillment of the Delivery Terms, unless otherwise provided in this Purchase Order, make payment within 30 days of receipt of the Supplier's invoice for the goods and copies of the shipping documents specified in this Purchase Order.

2.2 Payment against the invoice referred to above will reflect any discount shown under the payment terms of this Purchase Order, provided payment is made within the period required by such payment terms.

2.3 Unless authorized by UNDP, the Supplier shall submit one invoice in respect of this Purchase Order, and such invoice must indicate the Purchase Order's identification number.

2.4 The prices shown in this Purchase Order may not be increased except by express written agreement of UNDP.

3. TAX EXEMPTION

3.1 Section 7 of the Convention on the Privileges and Immunities of the United Nations provides, inter alia, that the United Nations, including its subsidiary organs, is exempt from all direct taxes, except charges for utilities services, and is exempt from customs duties and charges of a similar nature in respect of articles imported or exported for its official use. In the event any governmental authority refuses to recognize UNDP's exemption from such taxes, duties or charges, the Supplier shall immediately consult with UNDP to determine a mutually acceptable procedure.

3.2 Accordingly, the Supplier authorizes UNDP to deduct from the Supplier's invoice any amount representing such taxes, duties or charges, unless the Supplier has consulted with UNDP before the payment thereof and UNDP has, in each instance, specifically authorized the Supplier to pay such taxes, duties or charges under protest. In that event, the Supplier shall provide UNDP with written evidence that payment of such taxes, duties or charges has been made and appropriately authorized.

4. RISK OF LOSS

Risk of loss, damage to or destruction of the goods shall be governed in accordance with Incoterms 2010, unless otherwise agreed upon by the Parties on the front side of this Purchase Order.

5. EXPORT LICENCES

Notwithstanding any INCOTERM 2010 used in this Purchase Order, the Supplier shall obtain any export licences required for the goods.

6. FITNESS OF GOODS/PACKAGING

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

The Supplier warrants that the goods, including packaging, conform to the specifications for the goods ordered under this Purchase Order and are fit for the purposes for which such goods are ordinarily used and for purposes expressly made known to the Supplier by UNDP, and are free from defects in workmanship and materials. The Supplier also warrants that the goods are contained or packaged adequately to protect the goods.

7. INSPECTION

7.1 UNDP shall have a reasonable time after delivery of the goods to inspect them and to reject and refuse acceptance of goods not conforming to this Purchase Order; payment for goods pursuant to this Purchase Order shall not be deemed an acceptance of the goods.

7.2 Inspection prior to shipment does not relieve the Supplier from any of its contractual obligations.

8. INTELLECTUAL PROPERTY INFRINGEMENT

The Supplier warrants that the use or supply by UNDP of the goods sold under this Purchase Order does not infringe any patent, design, trade-name or trade-mark. In addition, the Supplier shall, pursuant to this warranty, indemnify, defend and hold UNDP and the United Nations harmless from any actions or claims brought against UNDP or the United Nations pertaining to the alleged infringement of a patent, design, trade-name or trade-mark arising in connection with the goods sold under this Purchase Order.

9. RIGHTS OF UNDP

In case of failure by the Supplier to fulfil its obligations under the terms and conditions of this Purchase Order, including but not limited to failure to obtain necessary export licences, or to make delivery of all or part of the goods by the agreed delivery date or dates, UNDP may, after giving the Supplier reasonable notice to perform and without prejudice to any other rights or remedies, exercise one or more of the following rights:

9.1 Procure all or part of the goods from other sources, in which event UNDP may hold the Supplier responsible for any excess cost occasioned thereby.

9.2 Refuse to accept delivery of all or part of the goods.

9.3 Cancel this Purchase Order without any liability for termination charges or any other liability of any kind of UNDP.

10. LATE DELIVERY

Without limiting any other rights or obligations of the parties hereunder, if the Supplier will be unable to deliver the goods by the delivery date(s) stipulated in this Purchase Order, the Supplier shall (i) immediately consult with UNDP to determine the most expeditious means for delivering the goods and (ii) use an expedited means of delivery, at the Supplier's cost (unless the delay is due to Force Majeure), if reasonably so requested by UNDP.

11. ASSIGNMENT AND INSOLVENCY

11.1. The Supplier shall not, except after obtaining the written consent of UNDP, assign, transfer, pledge or make other disposition of this Purchase Order, or any part thereof, or any of the Supplier's rights or obligations under this Purchase Order.

11.2. Should the Supplier become insolvent or should control of the Supplier change by virtue of insolvency, UNDP may, without prejudice to any other rights or remedies, immediately terminate this Purchase Order by giving the Supplier written notice of termination.

12. USE OF UNDP OR UNITED NATIONS NAME OR EMBLEM

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

The Supplier shall not use the name, emblem or official seal of UNDP or the United Nations for any purpose.

13. PROHIBITION ON ADVERTISING

The Supplier shall not advertise or otherwise make public that it is furnishing goods or services to UNDP without specific permission of UNDP in each instance.

14. CHILD LABOUR

The Supplier represents and warrants that neither it nor any of its affiliates is engaged in any practice inconsistent with the rights set forth in the Convention on the Rights of the Child, including Article 32 thereof, which, inter alia, requires that a child shall be protected from performing any work that is likely to be hazardous or to interfere with the child's education, or to be harmful to the child's health or physical, mental, spiritual, moral or social development.

Any breach of this representation and warranty shall entitle UNDP to terminate this Purchase Order immediately upon notice to the Supplier, without any liability for termination charges or any other liability of any kind of UNDP.

15. MINES

The Supplier represents and warrants that neither it nor any of its affiliates is actively and directly engaged in patent activities, development, assembly, production, trade or manufacture of mines or in such activities in respect of components primarily utilized in the manufacture of Mines. The term "Mines" means those devices defined in Article 2, Paragraphs 1, 4 and 5 of Protocol II annexed to the Convention on Prohibitions and Restrictions on the Use of Certain Conventional Weapons Which May Be Deemed to Be Excessively Injurious or to Have Indiscriminate Effects of 1980.

Any breach of this representation and warranty shall entitle UNDP to terminate this Purchase Order immediately upon notice to the Supplier, without any liability for termination charges or any other liability of any kind of UNDP.

16. SETTLEMENT OF DISPUTES

16.1 **Amicable Settlement.** The Parties shall use their best efforts to settle amicably any dispute, controversy or claim arising out of, or relating to this Purchase Order or the breach, termination or invalidity thereof. Where the Parties wish to seek such an amicable settlement through conciliation, the conciliation shall take place in accordance with the UNCITRAL Conciliation Rules then obtaining, or according to such other procedure as may be agreed between the Parties.

16.2 **Arbitration.** Unless, any such dispute, controversy or claim between the Parties arising out of or relating to this Purchase Order or the breach, termination or invalidity thereof is settled amicably under the preceding paragraph of this Section within sixty (60) days after receipt by one Party of the other Party's request for such amicable settlement, such dispute, controversy or claim shall be referred by either Party to arbitration in accordance with the UNCITRAL Arbitration Rules then obtaining, including its provisions on applicable law. The arbitral tribunal shall have no authority to award punitive damages. The Parties shall be bound by any arbitration award rendered as a result of such arbitration as the final adjudication of any such controversy, claim or dispute.

17. PRIVILEGES AND IMMUNITIES

Nothing in or related to these General Terms and Conditions or this Purchase Order shall be deemed a waiver of any of the privileges and immunities of the United Nations, including its subsidiary organs.

DocuSign Envelope ID: 3305CE2E-895C-43CF-9688-3550DD5646C5

18. SEXUAL EXPLOITATION:

18.1 The Contractor shall take all appropriate measures to prevent sexual exploitation or abuse of anyone by it or by any of its employees or any other persons who may be engaged by the Contractor to perform any services under the Contract. For these purposes, sexual activity with any person less than eighteen years of age, regardless of any laws relating to consent, shall constitute the sexual exploitation and abuse of such person. In addition, the Contractor shall refrain from, and shall take all appropriate measures to prohibit its employees or other persons engaged by it from, exchanging any money, goods, services, offers of employment or other things of value, for sexual favors or activities, or from engaging in any sexual activities that are exploitive or degrading to any person. The Contractor acknowledges and agrees that the provisions hereof constitute an essential term of the Contract and that any breach of this representation and warranty shall entitle UNDP to terminate the Contract immediately upon notice to the Contractor, without any liability for termination charges or any other liability of any kind.

18.2 UNDP shall not apply the foregoing standard relating to age in any case in which the Contractor's personnel or any other person who may be engaged by the Contractor to perform any services under the Contract is married to the person less than the age of eighteen years with whom sexual activity has occurred and in which such marriage is recognized as valid under the laws of the country of citizenship of such Contractor's personnel or such other person who may be engaged by the Contractor to perform any services under the Contract.

19. OFFICIALS NOT TO BENEFIT:

The Contractor warrants that no official of UNDP or the United Nations has received or will be offered by the Contractor any direct or indirect benefit arising from this Contract or the award thereof. The Contractor agrees that breach of this provision is a breach of an essential term of this Contract.

20. AUTHORITY TO MODIFY:


Pursuant to the Financial Regulations and Rules of UNDP, only the UNDP Authorized Official possess the authority to agree on behalf of UNDP to any modification of or change in this Agreement, to a waiver of any of its provisions or to any additional contractual relationship of any kind with the Contractor. Accordingly, no modification or change in this Contract shall be valid and enforceable against UNDP unless provided by an amendment to this Agreement signed by the Contractor and jointly by the UNDP Authorized Official.

Certificate Of Completion

Envelope Id: 3305CE2E895C43CF96883550DD5646C5
Status: Completed
Subject: Please DocuSign: RFQ1925 Reconstruction works UN House building.docx
Source Envelope:
Document Pages: 46
Signatures: 1
Envelope Originator:
Certificate Pages: 5
Initials: 4
Olga Driga
AutoNav: Enabled
olga.driga@undp.org
EnvelopeId Stamping: Enabled
IP Address: 87.255.68.247
Time Zone: (UTC-08:00) Pacific Time (US & Canada)

Record Tracking

Status: Original
6/10/2019 6:41:10 AM
Holder: Olga Driga
olga.driga@undp.org
Location: DocuSign

Signer Events	Signature	Timestamp
Olga Driga olga.driga@undp.org Procurement Associate United Nations Development Program Security Level: Email, Account Authentication (None)	 Signature Adoption: Uploaded Signature Image Using IP Address: 87.255.68.247	Sent: 6/10/2019 6:43:35 AM Viewed: 6/10/2019 6:43:45 AM Signed: 6/10/2019 6:43:52 AM
Electronic Record and Signature Disclosure: Not Offered via DocuSign		
Denis Suschevici denis.suschevici@undp.org United Nations Development Program Security Level: Email, Account Authentication (None)	 Signature Adoption: Pre-selected Style Using IP Address: 85.238.37.115	Sent: 6/10/2019 6:43:54 AM Viewed: 6/10/2019 11:57:26 PM Signed: 6/10/2019 11:58:17 PM
Electronic Record and Signature Disclosure: Accepted: 2/18/2019 4:41:57 AM ID: e79b0495-f51d-4a1c-9cd2-f770dcd9a7aa		

In Person Signer Events	Signature	Timestamp

Editor Delivery Events	Status	Timestamp

Agent Delivery Events	Status	Timestamp

Intermediary Delivery Events	Status	Timestamp

Certified Delivery Events	Status	Timestamp

Carbon Copy Events	Status	Timestamp

Witness Events	Signature	Timestamp

Notary Events	Signature	Timestamp

Envelope Summary Events	Status	Timestamps
Envelope Sent	Hashed/Encrypted	6/10/2019 6:43:54 AM
Certified Delivered	Security Checked	6/10/2019 11:57:26 PM
Signing Complete	Security Checked	6/10/2019 11:58:17 PM

Envelope Summary Events	Status	Timestamps
Completed	Security Checked	6/10/2019 11:58:17 PM

Payment Events	Status	Timestamps

Electronic Record and Signature Disclosure

ELECTRONIC RECORD AND SIGNATURE DISCLOSURE

From time to time, United Nations Development Program (we, us or Company) may be required by law to provide to you certain written notices or disclosures. Described below are the terms and conditions for providing to you such notices and disclosures electronically through the DocuSign system. Please read the information below carefully and thoroughly, and if you can access this information electronically to your satisfaction and agree to this Electronic Record and Signature Disclosure (ERSD), please confirm your agreement by selecting the check-box next to 'I agree to use electronic records and signatures' before clicking 'CONTINUE' within the DocuSign system.

Getting paper copies

At any time, you may request from us a paper copy of any record provided or made available electronically to you by us. You will have the ability to download and print documents we send to you through the DocuSign system during and immediately after the signing session and, if you elect to create a DocuSign account, you may access the documents for a limited period of time (usually 30 days) after such documents are first sent to you. After such time, if you wish for us to send you paper copies of any such documents from our office to you, you will be charged a $0.00 per-page fee. You may request delivery of such paper copies from us by following the procedure described below.

Withdrawing your consent

If you decide to receive notices and disclosures from us electronically, you may at any time change your mind and tell us that thereafter you want to receive required notices and disclosures only in paper format. How you must inform us of your decision to receive future notices and disclosure in paper format and withdraw your consent to receive notices and disclosures electronically is described below.

Consequences of changing your mind

If you elect to receive required notices and disclosures only in paper format, it will slow the speed at which we can complete certain steps in transactions with you and delivering services to you because we will need first to send the required notices or disclosures to you in paper format, and then wait until we receive back from you your acknowledgment of your receipt of such paper notices or disclosures. Further, you will no longer be able to use the DocuSign system to receive required notices and consents electronically from us or to sign electronically documents from us.

All notices and disclosures will be sent to you electronically

Unless you tell us otherwise in accordance with the procedures described herein, we will provide electronically to you through the DocuSign system all required notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to you during the course of our relationship with you. To reduce the chance of you inadvertently not receiving any notice or disclosure, we prefer to provide all of the required notices and disclosures to you by the same method and to the same address that you have given us. Thus, you can receive all the disclosures and notices electronically or in paper format through the paper mail delivery system. If you do not agree with this process, please let us know as described below. Please also see the paragraph immediately above that describes the consequences of your electing not to receive delivery of the notices and disclosures electronically from us.

How to contact United Nations Development Program:

You may contact us to let us know of your changes as to how we may contact you electronically, to request paper copies of certain information from us, and to withdraw your prior consent to receive notices and disclosures electronically as follows:
To contact us by email send messages to: pavol.mates@undp.org

To advise United Nations Development Program of your new email address

To let us know of a change in your email address where we should send notices and disclosures electronically to you, you must send an email message to us at pavol.mates@undp.org and in the body of such request you must state: your previous email address, your new email address. We do not require any other information from you to change your email address.

If you created a DocuSign account, you may update it with your new email address through your account preferences.

To request paper copies from United Nations Development Program

To request delivery from us of paper copies of the notices and disclosures previously provided by us to you electronically, you must send us an email to pavol.mates@undp.org and in the body of such request you must state your email address, full name, mailing address, and telephone number. We will bill you for any fees at that time, if any.

To withdraw your consent with United Nations Development Program

To inform us that you no longer wish to receive future notices and disclosures in electronic format you may:

i. decline to sign a document from within your signing session, and on the subsequent page, select the check-box indicating you wish to withdraw your consent, or you may;

ii. send us an email to pavol.mates@undp.org and in the body of such request you must state your email, full name, mailing address, and telephone number. We do not need any other information from you to withdraw consent.. The consequences of your withdrawing consent for online documents will be that transactions may take a longer time to process..

Required hardware and software

The minimum system requirements for using the DocuSign system may change over time. The current system requirements are found here: https://support.docusign.com/guides/signer-guide-signing-system-requirements.

Acknowledging your access and consent to receive and sign documents electronically

To confirm to us that you can access this information electronically, which will be similar to other electronic notices and disclosures that we will provide to you, please confirm that you have read this ERSD, and (i) that you are able to print on paper or electronically save this ERSD for your future reference and access; or (ii) that you are able to email this ERSD to an email address where you will be able to print on paper or save it for your future reference and access. Further, if you consent to receiving notices and disclosures exclusively in electronic format as described herein, then select the check-box next to 'I agree to use electronic records and signatures' before clicking 'CONTINUE' within the DocuSign system.

By selecting the check-box next to 'I agree to use electronic records and signatures', you confirm that:

- You can access and read this Electronic Record and Signature Disclosure; and
- You can print on paper this Electronic Record and Signature Disclosure, or save or send this Electronic Record and Disclosure to a location where you can print it, for future reference and access; and
- Until or unless you notify United Nations Development Program as described above, you consent to receive exclusively through electronic means all notices, disclosures, authorizations, acknowledgements, and other documents that are required to be provided or made available to you by United Nations Development Program during the course of your relationship with United Nations Development Program.