

**Reconstruction and modernisation of the 'Ion
Creanga' Secondary School, plot no.
9201110.378, with the addition of ancillary
buildings, located in the municipality of
Ungheni, 151 Stefan cel Mare si Sfint Street**

(name of the project)

Form No. 7
WinCmeta

LOCAL QUOTATION No. 2-2-11 R

**Architectural solutions. Block B, B". Elevator installation works (2510 -
SA)**

Prepared at current prices:

No. No.	Standard code and resource code	Works and expenses	Unit of measurement	Quantity as per project data	Estimated value, lei	
					Per unit of measure incl. wages	Total incl. salary
1	2	3	4	5	6	7
		1. Installation work 1.1. Elevator				
1	MAsB01C	Installation of passenger elevators with automatic sliding doors in a covered shaft: lifting capacity up to 1,000 kg, 12 stops, shaft height 44 m Small items = 1.0200	elevator	1.00		
2	MAsB01D 1	For pcs stop, whether more or fewer than those specified in the elevator's specifications, add to or subtract from standards A and B Small parts = 1.0200	1 stop	-9.00		
3	MAsB01E1	For every metre of shaft height, whether greater or less than that specified in the elevator's specifications, the values in standards A and B are increased or decreased accordingly Miscellaneous materials = 1.0200	m	-37.40		
		<i>Total</i>	lei			
		Total Elevator Including salary				
		<i>Total</i>	lei			
		<i>Social security</i>	24 %			
		<i>Transport costs</i>	%			
		<i>Procurement and warehousing</i>	%			
		<i>Total</i>				
		<i>Overhead costs</i>	%			
		<i>Total</i>				
		<i>Budget surplus</i>	%			
		Total installation works				

1	2	3	4	5	6	7
		Including salary				
		2. Machinery and equipment				
		2.1. Elevator				
5	Bidder's price	Passenger elevator, energy efficiency class A+, load capacity – 630 kg, travel speed - 1.0 m/s, dimensions of the lift shaft: 2200 x 2150 mm, number of stops – 3, number of doors – 4, door dimensions 900 x 2000 (h) mm, elevator car travel height – 6.60 m - Installation of control panels inside the lift and on pcs floor, with facilities for blind and disabled passengers; - Car doors: 900 x 2000 mm, made of satin-finished stainless steel, fire resistance class EI 60; - Car interior: satin-finish stainless steel, automatic opening at side landings with two panels, full-height and full-width curtain-type obstacle protection across the entire door; - Control panel with microcontroller, made of mirror-finish satin-finish stainless steel, bottom-mounted collective system, white illumination button that turns red upon command recognition, white glass panel with high-resolution, easy-to-read MATRIX LED display, status indicator with symbols; stainless steel handrail inside the cabin with 40 mm diameter rounded ends, facilities for the visually impaired; - Satin-finish stainless steel cabin ceiling, emergency vent in the ceiling; - Two-way communication system, telephone alarm device; - Automatic passenger evacuation system in the event of a power cut; - Landing indicators and landing control box surface-mounted on the wall, touch buttons, aluminium cabin door threshold, aluminium landing door thresholds; - Cabin interior flooring – PVC carpet – resistant to 10,000 repeated passages with a chair or wheeled stretcher – certified by the Ministry of Health; - Cabin ventilation fan with recirculated air flow;	Set	1.00		

1	2	3	4	5	6	7
		- Automatic cabin lighting (ON/OFF) with LEDs, lift shaft lighting; - Load verification system – electronic scales; - Installation plans for the lift.				
		<i>Total</i>	lei			
		Total Elevator Including salary				
		<i>Total</i>	lei			
		<i>Supply and warehousing</i>	%			
		Total machinery and equipment Including wages				
		3. Commissioning and start-up work 3.1. Lift				
23	1-14-002-2	Passenger elevator for administrative buildings, with 10 stops, load capacity up to 1,000 kg, car travel speed 1.6 m/s	elevator	1.00		
24	1-14-002-4	If the number of stops is changed, the figure is reduced or added to standard 01-14-002-02	1 stop	-7.00		
		<i>Total</i>	lei			
		Total Elevator Including salary				
		<i>Total</i>	lei			
		<i>Social insurance</i>	24 %			
		<i>Total</i>				
		<i>Overheads</i>	%			
		<i>Total</i>				
		<i>Budget surplus</i>	%			
		Total commissioning and start-up works Including wages				
		Total	lei			
		Total estimate: Including salary				

Prepared by

(position, signature, surname, first name)

Verified

(position, signature, surname, first name)

